

3. MATERIAL

Upon award Michels will begin working on material procurement. Early engagement of the project materials will ensure a timely start, efficient installation, and on time completion.

Materials	1st Delivery	Final Delivery
Conduit	8 Weeks	10 Weeks
Handholes	8 Weeks	10 Weeks
Fiber	14 Weeks	18 Weeks
Splicing Materials	14 Weeks	18 Weeks

Product sheets can be found in Exhibit B. These are indicative of the product which is currently specified. However, Michels will request Nexus' assistance in verifying that the product specified meets the standards of Nexus' customers. In reference to the fiber cable specifically, Michels has specified product that meets the project timelines. But we are also working to dual source product from other Tier 1 vendors in advance of hearing what Nexus' customer final needs will be. With this in mind, we plan to start by installing only a single 288 in each direction, fully spliced and ready to light. We will continue with more cable installation in the following weeks, as we know more about Nexus' customer approved cable and its availability. We believe this will work to meet Nexus' immediate needs, but will also allow for flexibility to match the hyperscaler's needs.

Michels has a Receiving Inspection Report to track each material delivery. The report documents what was delivered, and will note if there was any damage to the material and/or equipment. Michels will add pictures to the report if damages are identified.

4. SAFETY

Michels consistently applies thorough and sensible safety guidelines at all our facilities and on every job. These guidelines are implemented as follows:

- *Personnel* – Michels' employees utilize the best tools, equipment, information, and are highly trained to perform our work safely and effectively. We use these high-quality resources to ensure that all employees have the knowledge and means necessary to perform their job as safely as possible. We accomplish this goal by hosting on-site daily job briefings, weekly safety meetings, and regular safety checks.
- *Public* – Often, the residents of neighboring communities are not factored into the safety plan for construction projects, but Michels recognizes the important role the public plays in any construction project. We also understand that members of the public are much more vulnerable to unsafe worksite conditions, and that is why we extend great effort to safeguard the public from the jobsite hazards. By doing so, we not only prevent harm to residents and bystanders, but we protect our company's and our client's reputation.
- *System* – By utilizing safe construction and operation techniques while building and installing the system, we not only protect the people working on the system, but we also protect the system itself. The successful completion of a project hinges on steady, consistent progress, with minimal setbacks. We avoid setbacks caused by damage to the system by avoiding installation shortcuts or other techniques that are inconsistent with fiber system construction best practices.